

BILANS ROBÓT ZIEMNYCH - droga 010KZ							
Pikjeta	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Catk. obj. wykopu	Catk. obj. nasypu	Obj. netto
0+008.7	0.7	4.1	0.0	0.00	0.00	0.00	0.00
0+020.1	0.0	8.2	4.0	70.02	3.95	70.02	-66.07
0+040.1	1.9	2.6	19.1	108.08	23.02	178.11	-155.09
0+060.3	3.6	1.8	55.5	44.14	78.52	222.25	-143.73
0+080.1	3.1	2.8	66.1	44.87	144.64	267.12	-122.48
0+100.1	2.7	3.0	58.1	57.45	202.75	324.57	-121.82
0+120.2	1.8	4.0	45.4	69.93	248.16	394.50	-146.34
0+140.2	1.1	5.0	29.0	89.88	277.16	484.38	-207.21
0+160.2	1.8	4.0	29.2	90.12	306.38	574.49	-268.12
0+180.2	1.5	4.2	33.1	81.56	339.50	656.05	-316.55
0+200.3	1.9	3.8	34.1	80.31	373.65	736.36	-362.71
0+220.3	1.5	4.3	34.0	81.74	407.61	818.10	-410.49
0+240.4	2.0	3.8	34.9	81.16	442.56	899.26	-456.71
0+260.2	1.6	3.8	35.9	75.12	478.48	974.39	-495.90
0+280.3	2.4	2.5	40.7	62.84	519.18	1037.22	-518.05
0+300.1	2.5	2.6	49.0	50.16	568.20	1087.38	-519.18
0+320.2	2.7	2.5	51.8	51.12	619.97	1138.50	-518.53
0+340.3	2.9	3.1	55.5	56.55	675.51	1195.05	-519.54
0+349.4	2.7	2.8	25.3	26.98	700.78	1222.03	-521.25
0+351.0	2.3	3.4	4.1	5.13	704.90	1227.16	-522.26
0+360.3	2.2	3.8	20.6	33.12	725.48	1260.28	-534.80
0+380.3	1.0	5.1	32.0	89.05	757.51	1349.33	-591.82
0+400.3	1.1	5.1	21.9	102.24	779.46	1451.57	-672.11
0+420.3	1.1	5.3	22.6	103.40	802.01	1554.97	-752.96
0+440.3	1.0	5.8	20.8	110.90	822.79	1665.87	-843.08
0+460.3	0.6	6.0	15.7	117.72	838.49	1783.60	-945.11
0+480.2	1.2	4.9	18.3	108.17	856.74	1891.77	-1035.03
0+500.4	1.2	4.7	24.9	97.00	881.61	1988.77	-1107.16
0+520.2	1.2	5.4	24.3	100.43	905.95	2089.20	-1183.26
0+540.3	1.5	4.8	26.6	102.19	932.59	2191.40	-1258.80
0+549.0	1.6	4.7	13.2	41.77	945.82	2233.17	-1287.35
0+550.4	2.3	3.7	2.8	6.02	948.58	2239.18	-1290.60
0+560.3	2.4	3.7	23.3	36.57	971.85	2275.75	-1303.90
0+580.3	2.4	3.3	47.8	69.40	1019.69	2345.15	-1325.45
0+600.3	2.7	3.3	50.7	65.39	1070.35	2410.53	-1340.18
0+620.3	1.6	5.5	42.2	86.78	1112.50	2497.31	-1384.81
0+640.4	0.0	8.1	16.2	136.22	1128.68	2633.53	-1504.85
0+660.2	0.0	7.8	0.7	157.10	1129.38	2790.63	-1661.25
0+680.3	0.6	6.9	6.1	147.29	1135.48	2937.92	-1802.44
0+700.3	0.6	6.8	11.5	136.03	1147.01	3073.96	-1926.95
0+720.4	0.0	8.4	5.8	151.54	1152.79	3225.50	-2072.71
0+740.3	0.9	7.3	9.3	154.00	1162.11	3379.50	-2217.38
0+760.5	0.0	9.3	9.5	165.75	1171.61	3545.24	-2373.63
0+780.7	0.0	9.7	0.0	189.63	1171.61	3734.88	-2563.26
0+799.6	0.0	12.0	0.0	203.98	1171.61	3938.86	-2767.25
0+800.5	0.0	15.6	0.0	11.88	1171.61	3950.74	-2779.13
0+820.7	0.0	15.3	0.0	311.76	1171.61	4262.50	-3090.89
0+840.5	0.0	19.4	0.0	344.90	1171.61	4607.40	-3435.79
0+860.5	0.0	18.4	0.0	378.20	1171.61	4985.60	-3813.98
0+880.6	0.0	15.6	0.0	340.51	1171.61	5326.11	-4154.50
0+900.7	0.0	13.4	0.0	291.98	1171.61	5618.08	-4446.47
0+920.5	0.0	14.9	0.0	280.13	1171.61	5898.22	-4726.61
0+940.6	0.0	14.1	0.0	290.97	1171.61	6189.19	-5017.58
0+949.6	0.0	14.1	0.0	127.15	1171.61	6316.34	-5144.73
0+950.8	0.0	17.7	0.0	17.87	1171.61	6334.21	-5162.60
0+960.6	0.0	17.9	0.0	175.18	1171.61	6509.39	-5337.77
0+980.5	0.0	18.8	0.0	365.75	1171.61	6875.13	-5703.52
1+000.6	0.0	16.3	0.0	351.71	1171.61	7226.85	-6055.24
1+020.5	0.0	19.5	0.0	356.91	1171.61	7583.76	-6412.15
1+039.6	0.0	15.3	0.0	331.77	1171.61	7915.54	-6743.92
1+040.6	0.0	11.5	0.0	13.98	1171.61	7929.52	-6757.90
1+060.6	0.0	10.9	0.0	224.12	1171.61	8153.64	-6982.03
1+080.6	0.0	9.1	0.0	200.36	1171.61	8353.99	-7182.38
1+100.0	0.5	7.7	5.3	163.12	1176.91	8517.11	-7340.21
1+105.2	5.7	2.7	16.3	26.92	1193.21	8544.04	-7350.82
1+108.8	7.2	1.4	23.4	7.32	1216.65	8551.35	-7334.70

Tab. 1/1 - Tabela robót ziemnych